SPECIAL DIVISION, MYSORE.

FORM OF ADVERTISEMENT.

Dated 2nd June 1928.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Special Division, Mysore, up to 2 P.M., on 22nd June 1928, for extending the Hotel Metropole at Mysore. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the 15th December 1928.

2. The plans, detailed estimates and the conditions may be seen at the Executive Engineer's Office at Lacy's Court building, between the hours of 11 A.M. and 5 P.M., on all working days.

3. Tenders should be submitted on printed forms without which no tender would be valid. The forms may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed :—

Description of work	Unit of work	Rate per unit
	As per separate statement	

4. Each tender must be accompanied by a deposit of Rs. 1,000 in cash or Government Promissory Notes, as earnest money and be superscribed "Tender for extending the Hotel Metropole Building at Mysore," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer of Mysore, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond : in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office, Special Division in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. No tender stating "percentage less than the lowest tender or as per estimated rates" will be accepted.

10. Once the tender has been accepted, no claim for any concessions or higher rates will be entertained.

11. The work should be executed as per Public Works Department specification.

12. The decision of the Chief Engineer in all matters *re* : measurements, rates, etc., shall be final and legally binding.

Abstract estimate of the approximate quantities of different items of work for extending the Hotel-Metropole, Mysore.

Serial No.	Item of work	Quantity	Per	Rate	
				In figures	In words
	Ground floor.			Rs. a p.	Rs.
1	Earthwork excavation and filling in basement in all sides.	210	C.yd.		
2	Jelly concrete in chunam mortar ...	2,900	C.ft.		
3	Burnt brick in mortar foundation and basement.	5,300	,,		
4	Brick in mortar: superstructure ...	7,500	,,		
5	Do arch work over doors and windows.	950	,,		
6	Providing and fixing 6" burnt stone slabs with rough dressing.	930	Sq.ft.		
7	Two line dressing the top and the face of slabs including jointing.	990	,,		
8	Providing and fixing British standard Section English or Tota Girders including hoisting fixing and painting complete with one coat of anticorrosive paint.	50·74	Cwt.		
9	Providing and fixing rolled steel joists including hoisting and painting with one coat of anticorrosive paint.	153	,,		
10	Providing and fixing 1¼" teakwood panelled doors as per existing design and scantlings—including brass fittings, etc., complete.	542	Sq.ft.		
11	Providing and fixing 1¼" teak wood windows half panelled and half glazed with iron bars and brass fittings, etc., complete.	385	,,		
12	Providing circular pillars with bars and capitals as per design.	6	Each		
13	Roofing with jack arched terrace without flat tiles, complete.	36·75	Sqrs.		
14	Plastering with chunam mortar ...	150·22	,,		
15	Providing and fixing Kadapa slab wall plates in mortar below joists cut to sizes.	655	Sq.ft.		
16	Providing cornice, bases and capitals for all out side pillars as per design.	28	Each		
17	Cornice with beading and key stone with plastering, etc., complete.	279	R.ft.		
18	Brick in mortar cornice 1' deep complete as per design.	536	,,		
19	Flooring with Kadapa slabs on 3" concrete bed and cement pointed.	18·61	Sqr.		
20	Flooring with First Class Yelahanka tiles over 3" concrete bed and cement pointed.	9·50	,,		
21	Flooring with 1½" teak wood planks with tongue and groove joints with necessary frame work below flooring including wax polishing, etc., complete.	1,140	Sq.ft.		
22	Painting with two coats of silicate paint ...	21·80	Sqrs.		
23	White and colour washing	150·00	,,		

Serial No.	Item of work	Quantity	Unit	Rate	
				In figures	In words
24	Removing the existing stair case from the present position and refixing in the new place with necessary repairs and cross girders, etc., complete.	Lump sum		Rs. a. p.	Rs.
25	Providing and fixing a teak wood servants ladder to first floor.	Do			
26	Providing an Exmet wall with Exmet at every 3rd course brick in mortar mixed with cement and mortar plastered over.	399	S.ft.		
27	Providing and fixing bolts and nuts to wall plates and joists used by the side of wall including punching hole, etc., complete.	Lump sum			
28	Removing and resetting Kadapa slabs wherever necessary for providing walls, etc.	Do			
29	Levelling and forming the ground ..	Do			
30	Boxing girders	Do			
31	Filling in basement with extra earth got from outside.	150	C.yd.		
	First floor.				
1	Burnt brick in mortar 'superstructure' ..	8,400	C.ft.		
2	Do arch work over doors and windows.	350	,,		
3	Providing and fixing 6" burnt stone slabs with rough dressing.	·50	S.ft.		
4	Providing and fixing British Standard English or tota girders including hoisting and fixing, complete with one coat of Anticorrosive paint.	51·86	Cwt.		
5	Providing and fixing rolled steel joists including hoisting and painting with one coat of Anticorrosive paint.	109·88	,,		
6	Providing and fixing 1¼" teak wood panelled doors as per existing design and scantlings including brass fittings, etc., complete.	480	Sq.ft		
7	Providing and fixing 1¼" teakwood windows ½ panelled and ½ glazed shutters with iron bars and brass fittings, etc., complete	293	,,		
8	Roofing with jack arched terrace with kappi in chunam and 2 courses of flat tiles, etc., complete.	26·49	Sqr		
9	Plastering with chunam mortar ...	149·82	,,		
10	Providing and fixing Kadapa slab wall plates in mortar below joists cut to sizes, etc.	403	Sq.ft.		
11	Providing cornices and bases and capitals for all outside pillars as per design.	28	Each		
12	Cornice with beading and key stone with plastering, etc., complete.	169	R.ft.		
13	Brick in mortar cornice 1 deep, complete as per design.	637	,,		
14	Flooring with 1st class Yelahanka tiles on 3" concrete bed and cement pointed.	36·60	Sqr.		
15	Painting with 2 coats of silicate paint ...	18·96	,,		
16	Providing an exmet wall with exmet at every 3rd course, brick in mortar mixed in cement and mortar plastered over.	1,065	Sq.ft.		

Serial No.	Items of works	Quantity	Unit	Rate	
				In figures	In words
17	Teakwood wrought and put up	138·67	C.ft.	Rs. a. p.	Rs.
18	Providing and fixing iron trusses as per design for the hall with teakwood purlins, including painting iron work with 2 coats of anticorrosive paint, etc., complete.	4	Each		
19	Roofing with 1st class Yelahanka tiles on 2" x 1" teakwood reepers including wood oiling to reepers.	32·68	Sqr.		
20	Providing and fixing diagonal trusses as per design.	4	Each		
21	Providing and fixing ridge tiles in mortar.	142	R.ft.		
22	Brick in mortar ornamental perforated parapet wall between pillars.	165	"		
23	Providing pendiments in brick in mortar cornice ornamentation, etc., complete.	2	Each		
24	Brick in mortar ornamental parapet wall above terrace alround as per existing design, complete.	251	R.ft.		
25	Ceiling hall with as bestos sheets, with necessary wooden frame work, etc., as per design.	1000	Sq.ft.		
26	Wood oiling ...	Lump sum			
27	Providing and fixing wrought iron rain water pipes with heads, bends, etc., complete.	210	R.ft.		
28	Providing and fixing cast iron ornamental railings with 2 coats of painting, etc., complete.	30			
29	Constructing cisterns and opening out outlet pipes in bath rooms.	Lump sum			
30	Providing and fixing teakwood glazed ventilators with double shutters as per design.	56	Sq.ft.		
31	Providing and fixing teakwood ½" planks for valleys.	108			
32	Providing and fixing zinc sheets for valleys	108			
33	Providing mortar bands in velleys and at ends of roof.	120	R.ft.		
34	Providing and fixing teakwood ornamental eave board as per existing design.	92			

V. V. KARVE,
Executive Engineer,
Special Division.

GOVERNMENT OF MYSORE, STORES PURCHASE COMMITTEE.

Notice No. S. P. C. 12918, dated 2nd June 1928.

Sealed Tenders will be received by the undersigned up to 12 noon on Monday the 25th June 1928 for the supply of cement required for the Mysore Government Departments during the year 1928-29.

Intending tenderers may obtain forms of tender from this office on payment of Re. 1 per set (in cash only).

Forms will not be sent by V. P. P.

By Order,
T. V. A. ISWARAN,
Secretary, Stores Purchase Committee.